



Whitley & Siddons Tabulations

TxDot Bid Tabs - TB-0307A

BEXAR IH 35 03/08/07 IM 0352(320)

BEXAR COUNTY
 56 WORKING DAYS DATE: 03/08/07
 ESTIMATED COST: 5,289,063.76 HWY. NO.: IH 35
 PROJECT NUMBER: IM 0352(320)
 ENGINEER:
 DESCRIPTION: PVMNT REPAIR, SC, SMA OVERLAY & PVMNT MA
 CHECK: 0.00 LENGTH 14.455 ORDER READ: 36

ENG. ESTIMATE -> \$5,289,063.76

- 1) HUNTER INDUSTRIES, LTD \$4,058,998.13
- 2) H. L. ZUMWALT CONSTR, INC \$4,114,022.17
- 3) CLARK CONSTR OF TEXAS, LTD \$4,147,949.15
- 4) J. D. RAMMING PAVING CO., LTD \$4,212,148.69
- 5) DEAN WORD CO, LTD. \$4,215,884.60
- 6) AUSTIN BRIDGE & ROAD, LP \$4,792,302.46

				ENG. EST.	CNTR 1 CNTR 4	CNTR 2 CNTR 5	CNTR 3 CNTR 6
01322021	EMBANKMENT (VEHICLE) (ORD COMP) (TY C)	CY	641.660	12.040	34.830 75.650	35.000 23.822	27.090 73.000
01342008	BACKFILL (TY A OR B)	CY	7,025.590	23.250	7.710 5.000	13.000 22.772	10.960 29.500
01502002	BLADING	HR	19.000	80.000	91.200 75.000	80.000 106.820	75.000 150.000
01582005	SPEC EXCAV WORK (ORIGINAL)	CY	2,352.560	27.360	30.560 51.110	15.000 12.263	17.910 12.000
03142021	EMULS ASPH (BS TRT) (MS-2 OR AE-P)	GAL	14,332.880	3.000	3.010 1.600	2.200 1.561	1.500 2.800
1 03162005	ASPH (AC-15P)	GAL	132,568.660	3.250	NB NB	2.100 NB	NB NB
1 03162346	AGGR(TY- PE GR-4 SAC-C)	CY	4,418.960	46.750	NB NB	37.000 NB	NB NB
03402004	D-GR HMA(METH) TY-A PG64-22	TON	2,823.340	71.370	59.930 67.200	70.000 71.889	87.350 70.000
03402047	D-GR HMA(METH) TY-C SAC-A PG70-22	TON	564.660	135.210	70.000 93.150	70.000 84.879	125.210 75.000
1 03462014	STONE-MTRX-ASPH SMA-D SAC-A PG76-22	TON	36,456.380	87.590	NB NB	70.000 NB	NB NB

03542051 PLANE ASPH CONC PAV (0" TO 1 1/2")	SY	5,837.540	2.350	1.620 2.500	1.200 2.642	5.000 3.500
04542006 HEADER TYPE EXPANSION JOINT	LF	1,266.670	84.000	66.500 66.500	73.500 80.500	66.500 70.000
05002001 MOBILIZATION	LS	1.000	394,000.000	324,344.000 181,500.000	450,000.000 236,799.787	151,130.000 520,000.000
05022001 BARRICADES, SIGNS AND TRAFFIC HANDLING	MD	4.000	6,500.000	3,153.000 9,700.000	8,000.000 3,267.090	1,944.000 4,000.000
05062034 TEMPORARY SEDIMENT CONTROL FENCE	LF	240.000	5.040	4.000 5.000	2.650 4.240	5.000 10.000
05332001 SHOULDER TEXTURING (MILLED)	STA	474.250	20.000	42.500 12.450	16.000 36.551	32.300 50.000
06622113 WK ZN PAV MRK SHT TERM (TAB) TY W	EA	7,526.000	1.100	1.000 1.000	1.000 1.134	1.000 1.500
06722017 REFL PAV MRKR TY II-C-R	EA	1,598.000	3.980	3.100 3.100	3.400 3.100	3.100 3.100
61102015 REF PAV MRK TY I (W) (4") (BRK) (100 MIL)	LF	23,713.000	0.320	0.250 0.250	0.270 0.245	0.250 0.250
61102018 REF PAV MRK TY I (W) (4") (SLD) (100 MIL)	LF	94,850.000	0.320	0.240 0.250	0.250 0.238	0.240 0.240
61102036 REF PAV MRK TY I (W) (8") (SLD) (100 MIL)	LF	9,052.000	0.630	0.450 0.450	0.500 0.445	0.450 0.450
61102051 REF PAV MRK TY I (W) (24") (SLD) (100 MIL)	LF	2,250.000	5.250	4.860 4.860	5.350 4.860	4.860 4.860
61102057 REF PAV MRK TY I (Y) (4") (SLD) (100 MIL)	LF	94,850.000	0.350	0.240 0.240	0.260 0.234	0.240 0.230
61102108 REF PAV MRK SEALER (4")	LF	213,413.000	1.120	0.100 0.100	0.100 0.092	0.100 0.090
61102111 REF PAV MRK SEALER (8")	LF	9,052.000	0.250	0.250 0.250	0.270 0.250	0.250 0.250
61102113 REF PAV MRK SEALER (24")	LF	2,250.000	2.320	1.000 1.000	1.100 1.000	1.000 1.000
1A 03162005 ASPH (AC-15P)	GAL	132,568.660	3.250	2.720 2.250	NB 2.281	NB 3.000
1A 03162346 AGGR(TY-PE GR-4 SAC-C)	CY	4,418.960	46.750	62.030 56.650	NB 52.263	NB 66.000
1A 03422002 PFC (ASPHALT) PG76-22	TON	1,882.480	286.280	78.590 88.000	NB 86.514	NB 88.000
1A 03422006 PFC (AGGREGATE) (PG76 MIX) SAC-A	TON	29,492.100	90.000	78.590 88.000	NB 86.514	NB 88.000

1B 30002001 TBPFC (MEMBRANE)	GAL	143,616.050	2.120	NB NB	NB NB	2.000 NB
1B 30002003 TBPFC (AGGREGATE)	TON	29,492.100	90.000	NB NB	NB NB	95.310 NB
1B 30002004 TBPFC (ASPHALT) (PG 76-22)	TON	1,882.480	463.160	NB NB	NB NB	95.310 NB
1C 30002001 TBPFC (MEMBRANE)	GAL	132,568.510	2.120	NB NB	NB NB	NB NB
1C 30002003 TBPFC (AGGREGATE)	TON	29,492.100	90.000	NB NB	NB NB	NB NB
1C 30002005 TBPFC (ASPHALT) (A-R)	TON	1,882.480	475.600	NB NB	NB NB	NB NB